PIVOT ®

Model:

PVC10-SBUX-CAFE-MST1

Starbucks® Double Espresso Cart

Project:





PVC10-SBUX-CAFE-MST1

- Premium Coffee Cart
- Approx. 9 ft (Length) by 34 in (Depth) by 8 ft (Height)
- Complete Metal Construction
- Satin Black Powder Coat
- Beautiful Walnut Veneers
- Quartz Countertops
- Supports 2 Mastrenas
- Self-Contained Water/WasteWater
- Fully Installed Electrical with Load
 Center
- Features Refrigerator, Hand Sink, & Espresso Rinser
- LED Lights in the Canopy
- Lockable Storage with Shelves
- Assembled Installs in Minutes

ROUGH-IN DATA

	Cart Dimension (inches) (cm)			Weight	Voltage	AMPS	· •	Construction Countertops	Coffee	Lighting Type
Model	L	D	Н	(kg) no equipment			(Sewage)			,
PVC10-SBUX-CAFE-MST1	108 274	34 86	96 243	1,514 687	120/208V 3PH	60	Self-Contained Self-Contained	CRS/SS/AL Quartz	Espresso	LED



PIVOT ®

Model:

PVC10-SBUX-CAFE-MST1

Starbucks® Double Espresso Cart

Project:

STANDARD FEATURES

DESIGN

- Starbucks[®] Double Espresso Cart
- Designed as a Rear Line Cart to form a Starbucks[®] Cart Cafe
- Signature PIVOT Box Canopy design
- Supports two Mastrenas (available from Starbucks[®] sold separately)
- Features a Hand Sink, Espresso Rinser (with Hot Water Dispenser and Water Tower), and a 48 inch refrigerator
- · Recessed LED Ceiling Lights
- Beautiful and Updatable furniture grade Walnut Veneers
- Quartz Countertop Crystal Black
- Lockable Storage with Shelves
- Industrial Wheels Rear Locking
- Finished Roof System

DIMENSION

 Approximately - 9 ft (Length) by 34 inches (Depth) by 8 ft (Height)

CONSTRUCTION

- Base Construction STEEL
- Canopy ALUMINUM
- · Countertops Quartz

MATERIAL FINISH

- Powder Coated Steel SATIN BLACK
- Veneers WALNUT PREMIUM WOOD

UTILITIES

- Electric 120/208V 3PH 60AMP
- Wiring MC Cable
- Self-Contained Water Supply Utilizes 5
 Gallon filtered water bottles (not provided)
- Self-Contained Sewage Utilizes 7 Gallon

waste water container (provided)

LIGHTING

 LED Lights - TOTAL 19.5 Watts for Low Energy Consumption - 3000K (Warm White)

WEIGHT

 Approximately 1,514 lbs dry weight (no Equipment)

INSTALLATION

- Cart comes pre-assembled from the factory
- Canopy installs in approximately 45 minutes

CERTIFICATION

• UL LISTED



PLAN VIEW



